

ADDENDUM NO. 3

PARTICULARS

DATE: March 20, 2025

PROJECT: Troy University – Wallace Hall Reroof, DCM # 2025148

ARCHITECT: Seay, Seay & Litchfield, P.C. (SS&L Project No: 24174)

TO: PROSPECTIVE BIDDERS:

This Addendum is hereby made part of the Contract Documents, dated February 27, 2025, to the same extent as though it was originally included therein. Acknowledge receipt of this Addendum in the space provided in the proposal form. Failure to do so may disqualify the bidder.

1.01 CLARIFICATIONS / MODIFICATIONS:

- A. Please see the RFI log attached
- B. Based on information obtained during the core extraction process, bidders shall include the following roof requirements in their bids.
 - 1. All roof areas are to receive an approved 1/2" coverboard which shall be installed over the new tapered insulation system with low-rise foam adhesives approved by the roofing manufacturer.
 - 2. All new roof membranes shall be fully adhered per the project specifications and manufacturer's requirements.
 - 3. Any existing equipment, curbs, penetrations, etc. which may require removal, elevation alterations, etc. will be the responsibility of the installing contractor.

1.02 DRAWINGS:

- A. None

1.03 SPECIFICATIONS:

- A. 07 5410 Thermoplastic Polyolefin Roofing Membrane – TPO
 - a. 2.01 Acceptable Manufacturer, add “D. Duro-last” and “E. Elevate”

END OF SECTION

